

Installer Summary





For 0 to 1% slopes, *Absorption Width* is measured from the *Bed* equally in both directions. For slopes >1%, *Absorption Width* is measured downhill from the upslope edge of the *Bed*.

Rock Bed:	17.0 yd ³ or *1.4=	24 ton	9 inches under pipe
Mound Sand:	183 yd ³ or *1.4=	256 ton	calculation based on 3:1/4:1 slope from top of rockbe
Loamy Cap:	64 yd ³ or *1.4=	90 ton	6" deep
Topsoil:	74 yd ³ or *1.4=	104 ton	6" deep