


AITKIN COUNTY ENVIRONMENTAL SERVICES-PLANNING & ZONING
307 Second Street NW, Room 219
Aitkin, Minnesota 56431

PH: (218) 927-7342
FX: (218) 927-4372
aitkinpz@co.aitkin.mn.us



7/30/2020

Mark Olson
1906 Yorkshire Ave
Minnetonka, MN 55305

Re: Operating Permit #687
Zoning Permit # 2020006256
Parcel # 16-1-105200

Dear Permittee:

Enclosed is the Operating Permit for an "Other" Septic System (formerly Experimental, Performance, Etc.) that you are petitioning Aitkin County to allow to be installed on your property instead of a standard system. Please review this permit thoroughly and become acquainted with all of the conditions, then sign the operating permit and return it to the address above.

One provision that is often overlooked by homeowners is the State of Minnesota requirement that a water meter or other flow measuring device be installed and the results recorded by the homeowner on a REGULAR basis.

You will receive an annual reminder notice on how to renew your operating permit before the renewal expiration deadline. This reminder notice will ask that you provide:

- 1) Recorded water meter readings**
- 2) Annual Compliance Inspection report**
- 3) Renewal application and fee**

The Compliance Inspector/Service Provider is privately hired by you, the landowner. The Compliance Inspector/Service Provider must review the septic system on an annual basis. This annual review would be a great opportunity to review the conditions of the Operating Permit.

Should you have any questions, please contact our office.

Thank you,
Aitkin County Planning & Zoning

Enclosure: Operating Permit App

AITKIN COUNTY ENVIRONMENTAL SERVICES

**OPERATING PERMIT FOR WASTEWATER
TREATMENT AND DISPERSAL**

OPERATING PERMIT #: 687
ZONING PERMIT #: 2020006256
PARCEL #: 16-1-105200
PERMITTEE: Mark Olson

ORIGINAL DATE ISSUED: 7 /30/2020
RENEWAL PERIOD:
RENEWAL EXPIRATION: 5 /31/2023

MAILING ADDRESS: 1906 Yorkshire Ave
Minnetonka, MN 55305

PROPERTY ADDRESS:
32527 183rd St
Isle, MN 56342

TELEPHONE: (507) 848-5758

LEGAL: LOT 1 BLK 3 TRILLIUM S20, T44, 425

FEE PAID: 150 **DATE PAID:** 7 /29/2020 **RECEIPT:** 50672 **CK #:** card

Aitkin County Environmental Services authorizes the Permittee to operate a wastewater treatment and dispersal system located on the above described property in accordance with the requirements of this permit.

This permit is effective on the issuance date identified above.

This permit and the authorization to treat and disperse from the above system shall expire on the above expiration date. The Permittee is not authorized to discharge after the date of expiration. The Permittee shall submit such information and forms as required by Aitkin County Environmental Services no later than thirty (30) days prior to the expiration date. When the required information is submitted and approved by Aitkin County Environmental Services, the permit may be renewed. This permit is not transferable from owner to owner.

I hereby certify with my signature as the permittee that I understand the provisions of this permit including the maintenance and monitoring requirements. I agree to indemnify and hold Aitkin County harmless from all loss, damages, costs and charges that may be incurred by use of this system and if I fail to comply with the provisions of this Operating Permit. If I sell this property during the life of the permit, I will inform the new owner(s) of the permit requirements and the need to renew the permit.



Signature of Permittee

Date

Signature of Permitting Authority

Date

If you have any questions regarding this permit, including the specific permit requirements, permit reporting or permit compliance status, please contact Aitkin County Environmental Services at 218-927-7342.

A. DESCRIPTION OF WASTEWATER TREATMENT AND DISPERSAL SYSTEM

2 Bedroom Type III 'Other' Mound with 3 ft sandbase mound under 10'x25' rockbed, because of soil separation of 8".

B. PERFORMANCE STANDARD REQUIREMENTS:

During the period beginning on the effective date (issuance date) of this permit and lasting until this permit's expiration date, the Permittee is authorized to discharge from the wastewater treatment unit to subsurface dispersal. No surface discharge is permitted. The following parameters must be monitored and the results must be found within the compliance limits.

PARAMETER	COMPLIANCE LIMIT	SAMPLE LOCATION	SAMPLE FREQUENCY	SAMPLE TYPE	REPORTING FREQUENC
Seperation Distance	3 feet	Mound	Annually by inspector	Boring/measure in field	ANNUALLY to Aitkin Co.
Flow	300 GPD	Event Counter	Once/Month or when present	Record on a Log Sheet	ANNUALLY to Aitkin Co.

C. MAINTENANCE REQUIREMENTS:

PARAMETER	LOCATION	FREQUENCY
300 GPD	Read & Record Event Coutner	Once/Month or when present
Calibrate pump out gallons	Pump Chamber	ANNUALLY
Check dosing settings	control panel	ANNUALLY
Inspect for surface discharge	Mound area	ANNUALLY
Observe liquid level monitors	Dispersal System	ANNUALLY
Pumps, Floats & Alarms	Pump Chamber	ANNUALLY
Solids Removal & Water Tightness	Septic tank(s)	ANNUALLY

D. MONITORING AND REPORTING REQUIREMENTS:

Monitoring results obtained during each calendar year shall be submitted no later than May 31st of that year to:

Aitkin County Environmental Services
307 2nd Street NW, Room 219
Aitkin, MN 56431

The monitoring reports shall be signed by the Permittee. Copies are to be retained by the Permittee.

The Permittee shall notify Aitkin County Environmental Services within thirty (30) days when monitoring results do not meet the monitoring plan requirements of this permit.

Monitoring plans may be modified as necessary and reapproved by Aitkin County Environmental Services.

Sampling and laboratory testing procedures shall be performed in accordance with Standard Methods and shall be performed by a Minnesota Department of Health approved laboratory. All sampling and testing costs shall be the responsibility of the Permittee.

Monitoring will be performed by: Jeff Brummer

E. MITIGATION PLAN:

Have system inspected.