

**Tradewell Soil Testing  
18330 Dahlia Street NW  
Cedar, MN 55011**


Date: May 19<sup>th</sup>, 2008

Name: Scott Olmstead

Address: South 100' of Tract "C" in NW ¼ of Sec17 T44 R25 in Aitkin County

**SOIL BORING TEST REPORT**

<b>Boring #1</b>	<b>Boring #2</b>	<b>Boring #3</b>	<b>Boring #4</b>
0"- 4" Topsoil Fine Sandy Loam 10YR 2/2	0"- 4" Topsoil Fine Sandy Loam 10YR 2/2	0"- 12" Topsoil Fine Sandy Loam 10YR 2/2	0"- 8" Topsoil Fine Sandy Loam 10YR 2/1 2/2
4"- 30" Loamy Sand & Gravel 10YR 3/4 4/3	4"- 30" Loamy Sand & Gravel 10YR 3/4 4/4	12"- 26" Loamy Sand & Gravel 10YR 3/3 3/4	8"- 18" Loamy Sand & Gravel 10YR 3/3 3/4
30"- 46" Fine Sandy Loam & Gravel 7.5YR 3/4 4/4	30"- 44" Fine Sandy Loam & Gravel 5YR 3/4 4/4	26"- 36" Fine Sandy Loam & Gravel 7.5YR 3/4	18"- 32" Fine Sandy Loam & Gravel 7.5YR 3/4 4/4
Faint Mottles @ 28" Dry Hole	Faint Mottles @ 30" Dry Hole	Faint Mottles @ 30" Dry Hole	Mottles @ 16" Dry Hole



Mark Tradewell  
MPCA #307