Sherman Lumber, Inc.

2244 Hwy 65 * Mora, MN 55051						Chad Oelkers
(320) 640-9162 * Fax: (320) 679-4114		Sherman	•			(612) 390-0170
MN Lic. #BC004619		Buildings			ch	ad@shermanpb.com
Quote For: John McIntosh		Issue Date:	3/1/2023	Home:		
<u> </u>		Valid Until:	3/16/2023	Work:		
<u> </u>		Bid By:	ceo	Cell:		
		Bid #:	2.220840127	Fax:		
Aitkin	MN 564	31	Building site	is in	Aitkin	County
Size of Building: 20	8' 5.5" wall		Columns:	2x6 St	ud Walls	
Truss Spacing: 4 ' o.c	8' 0.5" Ceiling					
Purlins: 2x4 1650	.c. Flat		Eave	Stud V	/all	
Footing Material: K BracketC	thers	Trus	Truss Loading: 60 lb Snow Load			
Wall Girts: 2x4 1650			42	lb Live	Load	
All Colored Steel: Metal Sales Classic Rib 29 ga G6		G60		4	lb Dea	d Load
Overhangs:	Wainscoting:			7	lb Ceili	ng Load
Gable 1: Flush	Gable 1: 36 inch	<u> </u>		53	lb Tota	l Truss Load
Gable 2: Flush	Gable 2: 36 inch	1		House	Wrap:	All Walls
Eave 1: 6" Roof Steel	Eave 1: 36 inch	1		Ridge	Cap:	Metal
Eave 2: 6" Roof Steel	Eave 2: 36 inch	1		Ridge Cl	osure:	Vent Mesh
Accessories:	Ov	erhead Doors (WxH) - Bucked 1.5"			
1 - 36" Steel Service Door	1	-	12x7 ins ohd			gab 1
_						
2 - 36" x 36" window						
-						
-						
-	Oti	her: Debris Rem	oval Included			
Comments:						
* * * 10 YEAR WORKMANSH						
Constructed (On Your Prepare	ed Site Including	g Materials, T	ax, And	l Deli	very:
Customer is responsible for	r building permit.			7	otal:	\$16,998.31
	bid assumes s	tandard building and a	accessory colors			
ceilin	g height is measured f	rom top of future cond	rete floor to botton	of trusses		
Options:						
For an Excavation and Concr	ete Services quote, co	ontact Corey @ Sunde	erman Services at ((612) 390-7	424	

