City of Palisade Zoning PERMIT APPLICATION	on OTC.				
FULL NAME HILLIAND TELE # MAIL ADDRESS CITY STATE ZIP 911 ADDRESS OF PROPERTY 510 Marcon St. CITY STATE MN ZIP 5109 TOWNSHIP HOLD FOR LINE FINE LESS. SECTION TOWNSHIP RANGE 25 (circle) RESIDENTIAL COMMERCIAL ACCESSORY NEW BUILDING ALTERATION BUILDING CONTRACTOR AND LICENSE NUMBER: DESCRIBE YOUR PROJECT (IF APPLICABLE, INCLUDE DIMENSIONS OF ALL BUILDINGS CO	OFFICE USE ONLY DATE 48-10 (APPROVE) DENY PERMIT# 418.39 PARCEL# (10-0-001700) RECEIPT# CHECK # CONFORMING SEPTIC YES CI: NO (NEW) DVERED BY THIS APPLICATION)				
COMMENTS: DESIGNER: SLOTIC CALCE					
The undersigned hereby makes application for permit to construct as herein specified, agreeing to do all such work in strict accordance with the Ordinances of the County of Aitkin, Minnesota; Minnesota Individual Sewage Disposal Code Minimum Standards set forth by Minnesota Department of Health; and Shoreland Management Standards set forth by Minnesota Department of Natural Resources. Applicant agrees that plot plan, sketches and specifications submitted herewith and which are approved by the Zoning Official, shall become a part of the permit. APPLICANT FURTHER AGREES THAT NO PART OF THE SEWAGE SYSTEM SHALL BE COVEDED UNTIL THAS BEEN INSPECTED AND ACCEPTED. It shall be the responsibility of the applicant for the permit to notify the Zoning Office (at least 24 hours in advance) that the Septic System is ready for inspection. X SIGNATURE APPLICANT/AGENT DO NOT WRITE BELOW THIS LINE					
ZONING DISTRICT & FLOOD PLAIN ZONING DISTRICT (1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-	IVERVOTREAM				
PARCEL LOCATED IN FLOOD PLAIN? LAKE/RIVER/STREAM CLASSIF. SETBACK TO RO SETBACK TO BLI					
	SETBACK DISTANCES RUCTURES (10-ft. Tank/ 20-ft. Drainfield) IVER 25				
/	SETBACK (10-ft.)				
AFTER CONSTRUCTION YN SETBACK TO RO **ATTACH COPY OF ELEVATION CERTIFICATES** SOIL BORINGS SEPTIC DESIGN SEPTIC DESIGN SEPTIC TO RESTRICTING LAYER (circle) SSTS Type Type 1 Type 2 Type 3 Type 4	GARBAGE DISP/HOT TUB YES NO Type 5				
EXPIRES IN ONE YEAR • Aitkin County Zoning	1/ 1/4 22 1/ 2 1/				
Courthouse – 209 2nd St. NW. Room 100 • Aitkin, Minnesota 56431 \$	RECEIVED BY DATE				

Kristi Kunz

From:

Travis Johnson [Travis@septiccheck.com]

Sent:

Friday, April 08, 2016 2:54 PM

To:

Kristi Kunz <kristi.kunz@co.aitkin.mn.us> (kristi.kunz@co.aitkin.mn.us)

Subject:

Berglund Park

Attachments:

Burgland_Park_DOLI_planreview_coverletter.docx; ParkDWG.pdf;

pe_plumbreview_service_connection.pdf

Travis Johnson Production Manager



STOTE TIMES

A Division of WEX Companies, Inc. www.SepticCheck.com
6074 Keystone Road
Milaca, MN 56353
Phone: 320.983.2447

Cell: 320-630-4253 Fax: 320.983.2151 travis@septiccheck.com

This email has been scanned for email related threats and delivered safely by Mimecast. For more information please visit http://www.mimecast.com

INQPCL-1 Parcel Description 4/08/16
Data Set: PRD Production 14:56:05


Parcel/Acct : 60-0-001700 45130 Asmt/Tax year: 2015 2016 Type: RE Pri. owner : 90612 Hold tax stmt: Unit . . . : CITY OF PALISADE Emergency # : Lease Type: 90612 Taxpayer .: FALCO: 1 F.O. Escrow CITY OF PALISADE Surveyed .: Notes: UDI . : 100.00% Billing: P Com district: 5 Ref. parcel: Lake #/Name : 1060400 Mississippi Riv MH court nbr: TIF district: Physical adr: 510 Marconi St KD: User defined: PALISADE 56469 Acres . . : UTA-Twp/City: 60 PALISADE CITY 5.20 Lot/Block. 1 AITKIN School . .:

Plat/Desc : School . . : I AIIKIN

AMBU **** ****

ROW

Press Enter to continue or enter new parcel/tax year: 60-0-001700 2016 F1=Help F2=Trans History F3=Exit F6=Parcel History F7=Name/Addresses F8=Legal F24=More keys



340' from 04W of River. 44' from closest property line

30' from 500 line r-ow



Septic Check, Inc.

Septic System Management Services

2/16/2016

MN Dept of Labor & Industry Plumbing Plan Review 443 Lafayette Road N St Paul, MN 55155-4343

32	Owner:	City of Palisade	Project location:	Berglund Park
	Address:	P.O Box 144	Address:	510 Marconi Street
15	City, St, Zip:	Palisade MN 56469	City, St, Zip:	Palisade MN 56431

Enclosed please find a review application for Burgland Park in Aitkin County. The City of Palisade has proposed the installation of an RV sanitary dump station. The dump station design will be reviewed and permitted by Aitkin County Land Services per MN Rule 7080 and local ordinance.

Sewer line Plumbing Specifications:

The dump station will be connected to the tank using 4" SDR 26 PVC gasketed sewer pipe to meet ASTM standards D3034 and D2321. All piping will be laid on granular bedding. Uniform slope will be at least 1/8" per foot per MN Rules, part 4715.0570. The sewer line installation will be inspected and pressure tested prior to backfill per MN Rules, part 4715.2820, subp. 2.

Water line plumbing specifications:

The water supply for the dump station will be supplied by the existing 6" water main owned by the city of palisade. A new 1" waterline service will be used to connect the water main to the dump station tower and the outdoor water spigot. A minimum of a 10' horizontal setback will be maintained from the water service line to the sanitary sewer line. A potable water tower and shut off valve will be installed by the dump station and will be constructed per the MN plumbing code specifications. See attached drawing. A water spigot will be installed 60' northwest of the dump station. See attachment for detail.

Brian Koski		Date: 2/16/20)16				
Restricted Master Plumber Lic # 076687-MR							
Submittal includes:							
☐ Plan Cover letter	☐ Plumbing Description	☐ Plans signed by plumber	☐ Copies of Plumbing Certificates				

AITKIN COUNTY ZONING

PERMIT NUMBER 41839	PARCE NUMBE		001700			
Location PART OF LOT INE OF SOO LINE Lot Block Gov't Lot	27 Section	49	25			
RIW LESS CO RD ROW	Section	Twp.	kge.			
Issued April 8, 2016 To City of	Palisade					
Nature of Authorization Adding a 1500 gallon holding tank to be						
used as a dumpatation.	J					
New Construction Alteration		NOTE:				
Sewer Installation	This permit must be pon premises on which	n work is to be do	one and remain			
Flood Plain and Lowest Floor Elev	until work has been c	ompleted and ins	spected.			
This permit expires one year from date of issuance NOT TRANSFERABLE	ZONING ADMINISTRATOR					

No Portion of any Sewage Disposal System shall be Covered Prior to Inspection.